

# SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
	40	
1. Public Land Survey	T 51 R 41	A-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Recorded December 5 1994  
at 2:05 o'clock P. M. in  
Liber 3 page 225  
*J. M. Marley*  
Register of Deeds

Register of Deeds Stamp & File Number

Section Corner 19, 20 T51N R40W & 24, 25 T51N R41W

I, Earl W. Applekamp, in a field survey on September 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corners established by Austin Burt U.S. Deputy Surveyor, August 1848.  
Set Wood Post.  
Original Bearing Trees:

Hemlock	10"	N51°E	48 Links	(31.68')
Maple	16"	N11°E	15 Links	(9.90')

**ONTONAGON COUNTY  
PEER APPROVED**

*Earl W. Applekamp*  
Ont Co Rep  
11-30-94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner position is in the intersection of Townline and Quartz Road. A PK nail was in the blacktop at the intersection of the roads. The position was used to describe several parcels of land to the North. I accepted the intersection of the roads being the corner location and the roads being the boundary of numerous parcels of land in four directions. I replaced the PK nail with a permanent monument described below.

Research on file with County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 3/4" x 2' long aluminum rod with a 3/4" cap recessed in the blacktop and stamped to read: County Remonumentation S 19, 30, 24 & 25, T51N R40W, R41W, 1994, P.S. 17610. The following trees and objects were used to tie in the corner.

4"	Maple	N46°W	45.97'	-	Power Pole	S42°E	46.46'
6"	Spruce	N57°E	55.99'	-	Steel sign post	S64°W	33.64'



Signed by *Earl W. Applekamp* Date October 07, 1994  
Surveyor's Michigan License No. 17610