

**SURVEY &
REMONUMENTATION**

DEC 16 1996

COMMISSION

JUDITH D. ROEHM 04/02/96
Ontonagon County 14:31
LC 4/ 37 JEM Fee: 9.00
Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>Ontonagon</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>40W</u>	<u>B-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Joseph C. Domitrovich, in a field survey on September 26, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B-7) 1/4 corner common to Sections 18 & 19, T51N, R40W

1845 - William A. Burt set fir post
18" Y. Birch N 66° E 35 links
8" Cedar N 77° W 12 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

All remains of original bearing trees have been removed by farming. Original calls to streams along this section line are inconsistent with present stream crossings. A rotten corner fencepost at the intersection of a very old east-west fence and a fallen fence to the north are the only remaining evidence of the corner position.

This fence intersection has been the long occupied and accepted 1/4 corner position, therefore I have accepted it and Monumented it as such.

Research on file with County Remonumentation Representative.

PEER GROUP APPROVED
Paul W. Applekamp
COUNTY REPRESENTATIVE 3-27-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is an aluminum pipe with a 3" diameter stamped aluminum cap and falls at the intersection of fence east, west, and north.

Witnesses

10" Poplar	S 32° W	31.60'
4" Poplar	S 71° W	12.82'
8" Poplar	N 21° W	33.47'
6" fencepost	North	0.60'
Steel sign post	S 45° E	0.99'

NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by Joseph C. Domitrovich
37273

Date 3/26/96

Surveyor's Michigan License No. _____

