

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|---------------------------------------|-------------------|---------------|
| <u>Ontonagon</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>51NR 40W</u> | <u>E-4</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

COUNTY
REMONUMENTATION

OCT 3 0 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Joseph C. Domitrovich, in a field survey on June 9, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | ● | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

(E-4) 1/4 Corner Common to Sections 8 and 9, T51N, R40W

A. Description of original monument and accessories and/or subsequent restoration:

1845 - William A. Burt, D.S., set Sugar post.
 7" Fir S 45° W 12 links
 18" Hemlock N 65° E 21 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Original corner and accessories have been destroyed by logging and farming.

At the corner I found the intersection of fences North and West. This position works well with Section Corners North and South:
 NE Corner Section 8 N 00° 10' 42" E 2634.61'
 SE Corner Section 8 S 00° 11' 12" E 2628.62'

I accepted the fence intersection as the best position for the 1/4 corner and have monumented it as such.
 Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Corner is a 5/8" x 48" iron pin with a 3" diameter aluminum cap stamped: COUNTY REMONUMENTATION; T51N, R40W; 1/4; S. 8, S. 9; 1997; P.S. 37273. Corner falls 156 feet West of centerline of old railroad grade.

Witnesses:
 7" Hard Maple N 51° E 15.13'
 8" Hard Maple S 22° E 17.41'
 12" Poplar S 50° W 25.86'
 6" Poplar N 75° W 10.67'
 Steel Sign Post North 0.75'

PEER GROUP APPROVAL
Paul W. Applekamp
 COUNTY REPRESENTATIVE
 (to face) 6-10-97



NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.
 Signed by Joseph C. Domitrovich Date 6/9/97
 Surveyor's Michigan License No. 37273