

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Ontonagon County Remonumentation Corner

JOSEPH D. ROEHR

1F

Ontonagon County

Page 1 of 1

LC

5/ 65

JDR Rec. Date 05/26/98 Time 10:46

RECORDING FEE: 9.00

For corners in

Ontonagon County Located in: Corner Code #

- 1. Public Land Survey T51N R40W F-5
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R
- 4. Lot No. , Recorded Plat
- 5. Private Claims

SURVEY & REMONUMENTATION

JAN 11 1999

SECTION

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Joseph C. Domitrovich, in a field survey on May 7, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(F-5) ¼ Corner common to Sections 9 and 16, T51N, R40W

1845 - William A. Burt set a Hemlock Post: 12" Black Ash N42°E 38 links
21" Yellow Birch N72°W 39 links

I found no other record of subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found no remains of the original corner or accessories.

I reestablished corner by single proportionate measurement. Distances East and West to existing streams work well with GLO calls. Distances to Section Corners East and West also work well.


Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 2" x 30" aluminum pipe with a with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; T51N, R40W; ¼; S.9, S.16; 1998; P.S. 37273. Corner falls at the foot of a steep incline to the west.

Witnesses:

4" Balsam	N37°E	15.44'	
6" Ash	N75°E	3.27'	
6" Hard Maple	S39°E	25.20'	
12" Basswood	S33°W	16.63'	
Steel Sign Post	West	1.72' (to face)	
SW Cor. Sec. 9	N89°40'48"W	2648.07'	(2644.62 GLO)
SE Cor. Sec. 9	S89°40'48"E	2648.07'	(2644.62 GLO)



NOTE: Bearings are magnetic. Distances are to a nail in side of the witness object unless noted.

PEER GROUP APPROVED

Carl W. Applbaum
COUNTY REGISTER 5-13-98

Signed by J. C. Domitrovich

Date 5/13/98

Surveyor's Michigan License No. 37273