

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Ontonagon County Remonumentation Corner

Ontonagon County Page 1 of 1 LC 5/ 66 Rec. Date 05/26/98 Time 10:46 RECORDING FEE: 9.00

For corners in

- Ontonagon County Located in: Corner Code #
1. Public Land Survey T51N R40W G-4
2. Property Controlling in Section S S S S
3. Miscellaneous Property in Sec. S T
4. Lot No. , Recorded Plat
5. Private Claims

SURVEY & REMONUMENTATION

JAN 11 1999

SECTION

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column G and row 4.

I, Joseph C. Domitrovich, in a field survey on May 8, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: (G-4) 1/4 Corner common to Sections 9 and 10, T51N, R40W

1845 - William A. Burt set a Hemlock Post: 6" Maple N22°E 15 links 30" Hemlock N31°W 21 links

undated - Written by unknown person in copies of Original Field Notes on file at Ontonagon County Register of Deeds is the following: "Stump of Hemlock & Maples are here & Spruce blazed on 4 sides. Dis. From N. 2639.2"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I recovered the Original 30" Hemlock Bearing Tree, now a 36+" rotten stump with remains of Hemlock bark. I replaced the 1/4 corner from this B.T. I found no remains of the 6" Maple Bearing Tree. This position falls N55°E 12.16' from a 8" Maple blazed on three sides and N73°W 43.44' from a fallen wood post with aluminum Champion tag with "1978 Approx. Cor." facing on it.


Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 2" X 30" aluminum pipe with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; T51N, R40W; 1/4; S.9, S.10; 1998; P.S. 37273.

Witnesses:

- 4" Balsam S56°E 3.81'
4" Soft Maple S12°E 8.11'
8" Hard Maple S55°W 12.16' (Grown over blazes on three sides)
6" Soft Maple N67°W 5.75'
Steel Sign Post North 1.0'
NW Cor. Sec. 10 N00°02'53"W 2628.26'
SW Cor. Sec. 10 S00°20'52"E 2640.04'



NOTE: Bearings to witness objects are magnetic. Distances are to a nail in side of the witness object unless noted.

PEER GROUP APPROVED

Signature of Paul W. Applekamp, County Registrar, dated 5-13-98

Signed by Joseph C. Domitrovich

Date 5/13/98

Surveyor's Michigan License No. 37273