

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Ontonagon County Remonumentation Corner

ROEHN 1P
 Ontonagon County
 Page 1 of 1 LC 5/ 68
 JDR Rec. Date 05/26/98 Time 10:47
 RECORDING FEE: 9.00

For corners in

Ontonagon County Located in: Corner Code #

1. Public Land Survey T51N R40W G-7
 T R
 T R
 T R

2. Property Controlling S
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

4. Lot No. , Recorded Plat
 5. Private Claims

SURVEY &
 REMONUMENTATION

JAN 11 1999

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

SECTION

I, Joseph C. Domitrovich, in a field survey on April 20, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G-7) Corner of Sections 15, 16, 21 and 22, T51N, R40W

1845 - William A. Burt set a sugar post: 20" Yellow Birch S47°E 61 links
 36" White Pine N45°W 3 links

1981 - Neal Sperhake P.S. 7876, recovered the Original White Pine Bearing Tree and replaced corner from it. (Recorded in Liber 2, Page 122 of Corner Records) He placed a 3 foot iron pipe w/ alum. Cap stamped: T51N-R40W, 16,15,21,22 and scribed four N.B.T.'s:

5" Maple N24°E 8 feet 1 inch
 5" Maple S61°W 3 feet 8 inch
 7" Maple N30°W 18 feet 11 inch
 7" Maple S66°E 16 feet 9 inch

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found the remains of the 36" White Pine Bearing Tree, now a huge rotten stump. I also found the corner and all four accessories as called for by Sperhake. Joseph Stimac, resident of the area for over 60 years stated that in the 1930's there used to be a squared wood post where Sperhake now has his corner. I found no remains of the Yellow Birch B.T.

I accepted the corner as found and added a steel sign post w/ corner marker sign and nails to the sides of existing N.B.T.'s

Research on file with County Remonumentation Representative.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 1" galvanized pipe with a 4" aluminum cap stamped as indicated in Part A above, as well as "Kimberly Clark" and #7876. Corner falls at the base of a huge rotten stump.

Witnesses:

6" Hard Maple N23°E 8.00' (existing)
 8" Soft Maple S63°E 17.03' (existing)
 Steel sign post South 1.39' (to face)
 7" Soft Maple S62°W 3.42' (existing)
 7" Soft Maple N29°W 18.52' (existing)

PEER GROUP APPROVED
Earl W. Applbaum
 COUNTY SURVEYOR
 5-13-98



NOTE: Bearings are magnetic. Distances are to a nail in side of the witness object unless noted.

Signed by Joseph C. Domitrovich

Date 5/13/98

Surveyor's Michigan License No. 37273