

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
Ontonagon County Remonumentation Corner

Ontonagon County  
of 1 LC 5/ 94  
Rec. Date 06/25/98 Time 12:10  
RECORDING FEE: 9.00

For corners in

| Ontonagon County                   | Located in:   | Corner Code # |
|------------------------------------|---------------|---------------|
| 1. Public Land Survey              | T51N R40W     | I-4           |
|                                    | T R           |               |
|                                    | T R           |               |
|                                    | T R           |               |
| 2. Property Controlling In Section | S T R         |               |
|                                    | S T R         |               |
| 3. Miscellaneous Property in Sec.  | S T R         |               |
|                                    | S T R         |               |
| 4. Lot No.                         | Recorded Plat |               |
| 5. Private Claims                  |               |               |

SURVEY & REMONUMENTATION

JAN 11 1999

SECTION

Register of Deeds Stamp & File Number

|    | A  | B  | C  | D  | E  | F  | G  | H  | I  | J | K | L | M |
|----|----|----|----|----|----|----|----|----|----|---|---|---|---|
| 1  |    |    |    |    |    |    |    |    |    |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |    |    |    |   |   |   |   |
| 3  |    |    |    |    |    |    |    |    |    |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |    |    |    |   |   |   |   |
| 5  |    |    |    |    |    |    |    |    |    |   |   |   |   |
| 6  | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |
| 7  |    |    |    |    |    |    |    |    |    |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |    |    |    |   |   |   |   |
| 9  |    |    |    |    |    |    |    |    |    |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |    |    |    |   |   |   |   |
| 11 |    |    |    |    |    |    |    |    |    |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |    |    |    |   |   |   |   |
| 13 |    |    |    |    |    |    |    |    |    |   |   |   |   |

I, Joseph C. Domitrovich, in a field survey on June 15, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
(I-4) 1/4 Corner Common to Sections 10 & 11, T51N, R40W

- 1845 - William A Burt Set fir post
  - 12" Hemlock N 47° W 21 links
  - 14" Y. Birch N 74° E 31 links

No subsequent record found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found no remains of original corner or accessories. I found no other evidence indicating where the corner should be. Therefore, I re-established the 1/4 Corner by single proportionate measurement.

Distances to Corners North and South work well with original GLO.

Research on file with County Remonumentation Representative.


PEER GROUP APPROVED  
*Earl W. Applegate*  
COUNTY REPRESENTATIVE 6-17-98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 2 1/2" x 30" aluminum pipe with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; S. 10, S. 11; 1/4; T.51N, R.40W; 1998; P.S. 37273.

Witnesses:

|                    |                 |          |           |
|--------------------|-----------------|----------|-----------|
| 5" Hard Maple      | N 47° W         | 6.20'    |           |
| 8" Twin Soft Maple | S 85° E         | 23.89'   |           |
| 5" Twin Hard Maple | S 08° E         | 15.30'   |           |
| Steel Sign Post    | South           | 1.32'    | (to face) |
| 6" Twin Soft Maple | S 64° W         | 26.45'   |           |
| NE Cor. Section 10 | S 00° 06' 16" E | 2635.15' |           |
| SE Cor. Section 10 | N 00° 06' 16" W | 2635.15' |           |



NOTE: Bearings to witness objects are magnetic. Distances are to a nail in side of the witness object unless noted.  
Signed by *J. C. Domitrovich* Date 6-17-98

Surveyor's Michigan License No. 37273