

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Ontonagon County Remonumentation Corner

ROEHN
 Ontonagon County
 Page 1 of 1 LC 5-95
 JEM Rec. Date 06/25/98 Time 12:10
 RECORDING FEE: 9.00

For corners in

- Ontonagon County Located in: Corner Code #
- 1. Public Land Survey T51N R40W I-5
 T R
 T R
 T R
 - 2. Property Controlling S T R
 In Section S T R
 - 3. Miscellaneous S T R
 Property in Sec. S T R
 - 4. Lot No. , Recorded Plat
 - 5. Private Claims

SURVEY &
 REMONUMENTATION
 JAN 11 1998
 SECTION
 Register of Deeds Stamp & File Number

I, Joseph C. Domitrovich, in a field survey on June 10, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(I-5) Corner Common to Sections 10, 11, 14 & 15, T51N, R40W

- 1845 - William A. Burt set a post
 6" Black Ash S 85° W 13 links
 24" Hemlock N 72° E 24 links

No subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found no remains of the original corner or accessories. I found a 6" Soft Maple squared on four sides with 1975 Champion tag indicating this is the approximate Section Corner. Extensive retracement to the North, South, East, and West indicates this corner to be out of position.

I re-established the corner position by double proportionate measurement between the Section Corner one mile to the West, the Section Corner one mile to the North, the Section Corner one mile to the South, and the centerline of North-South Norwich Road (1/4 line road) to the East. Distances in all directions work well with this position. The squared Maple falls 25 feet East and 7 feet South of this position.

Research on file with County Remonumentation Representative.

PEER GROUP APPROVED
Paul W. Applekamp
 COUNTY REPRESENTATIVE 6-17-98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 2 1/2" x 30" aluminum pipe with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; S.10, S. 11, S.14, S. 15; T.51N, R.40W; 1998; P.S. 37273. Corner falls in the bottom of a shallow ravine.

8" White Ash	S 07° E	27.66'	
4" Hard Maple	N 77° W	37.98'	
6" Y. Birch	N 38° E	9.93'	
6" Soft Maple	S 73° E	26.17'	(squared on 4 sides—Champion approx. corner)
Steel Sign Post	North	0.93'	(to face)
NE Cor. Section 10	N 00° 06' 16" W	5270.30'	(5280' GLO)
SE Cor. Section 15	S 00° 05' 00" E	5270.30'	(5280' GLO)
NW Cor. Section 15	N 89° 53' 53" W	5268.62'	(5269.44' GLO)
Centerline Norwich Rd.	East	2649.50'	(2649.9' GLO)

NOTE: Bearings to witness objects are magnetic. Distances are to a nail in side of the witness object unless noted.

Signed by Joseph C. Domitrovich Date 6-17-98

Surveyor's Michigan License No. 37273

