

JUDITH D. ROEHN

Ontonagon County

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Page 1 of 1
JEN Date 10/27/1999 Time 10:10:35
RECORDING FEE: 2.00

U. 5/228

For corners in

| | | |
|------------------------------------|---------------|---------------|
| Ontonagon County | Located in: | Corner Code # |
| 1. Public Land Survey | T51N R40W | I - 6 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |
| 4. Lot No. | Recorded Plat | |
| 5. Private Claims | | |

SURVEY & REMONUMENTATION

MAR 23 2000

SECTION

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Joseph C. Domitrovich, in a field survey on October 5, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I-6) 1/4 Corner common to Sections 14 and 15, T51N, R40W.

1845 William A Burt set a yellow birch post with ties:

| | | |
|------------------|--------|----------|
| 12" Yellow Birch | N 76°E | 17 links |
| 10" Black Ash | S 64°W | 16 links |

I found no record of subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found no remains of the original corner or accessories. I re-established the corner position by single proportionate measurement. Distances to section corners to the North and South work well with GLO:

| | | |
|----------------------|--------------|----------|
| NW Corner Section 15 | N 00°04'57"W | 2635.14' |
| SW Corner Section 15 | S 00°04'57"E | 2635.14' |

Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 2 1/2" x 30" diameter aluminum pipe with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; T51N, R40W; S.15, S.14; 1/4; 1999; P.S. 37273. Ties:

| | | |
|-----------------|--------|-----------------|
| 4" Poplar | S 56°E | 14.81' |
| Steel sign post | South | 1.08' (to face) |
| 8" Soft Maple | S 36°W | 21.43' |
| 8" Soft Maple | N 33°W | 31.44' |

NOTE: Bearings to witness objects are magnetic. Distances are to a nail in side of the witness object unless noted.

PEER GROUP APPROVED

Ed W. Applekamp 10-14-99
COUNTY REMONUMENTATION

Signed by Joseph C. Domitrovich

Date 10-14-99

Surveyor's Michigan License No. 37273

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

