

# SURVEY & REMONUMENTATION

APR 25 1995

## COMMISSION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Ontonagon

(County)

Located In:

Corner Code ##

- |                                    |                           |       |
|------------------------------------|---------------------------|-------|
| 1. Public Land Survey              | T <u>51N</u> R <u>40W</u> | K8    |
|                                    | T _____ R _____           | _____ |
|                                    | T _____ R _____           | _____ |
|                                    | T _____ R _____           | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____ |
|                                    | S _____ T _____ R _____   | _____ |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____ |
|                                    | S _____ T _____ R _____   | _____ |

Recorded December 19 1994  
at 2:30 o'clock P. M. in  
Liber Survey 3 page 244  
*Julie M. Marley*  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on August 29, 1994, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Quarter corner common to Sections 23-24. Corner established in 1845 by Wm A. Burt as follows: "Set sugar post Qr. Section corner, Sugar 8 N37E 30, do 6 N42W 21". Corner recorded pursuant to Act 74, P.A. 1970 by Keith L Sackett, RLS #19006, in 1977 as follows: "Re-established on line between Section corners. Set 1" I.D. by 5 foot long iron pipe. 6" Maple N88W 17.8' 1/4S NBT, 5" Maple S79E 27.1' 1/4S NBT, 6" maple N53W 1.9' squared and marked 1/4 23,24". Found no subsequent record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Recovered the monument placed in 1977, as described, and at record bearing and distance from the 1977 accessories. Determined that the monument placed in 1977 is 10.6' east and 6.8' north of the position proportionate to the original record, and, as it appears not to have been relied upon since 1977, I rejected it as monumenting the 1/4 corner. Reestablished the corner on a straight line between monumented section corners, previously recorded pursuant to Act 74, P.A. 1970, and being 2623.37' north and 2623.37' south. The 1977 monument, which bears N60E 12.6' from the corner, was left in place.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Placed a 3/4" dia.x48" long aluminum rod capped with a 3 1/4" dia aluminum cap stamped: "County Remonumentation T51N R40W 1/4 23\24, 8-29-94, PS33986" from which bear the following:  
10" Maple N51E 11.7' mrkd "1/4S NBT"  
6" Sugar S75W 24.9' do  
10" Maple N25W 10.7' do  
5" Ash S20E 45.8' do  
metal sign post S85W 1.0'  
Distances are to notch in lower blaze.  
Bearings are magnetic.



**ONTONAGON COUNTY  
PEER APPROVED**

*Earl W. Applbaum*  
Ont. Co. Rep.  
12-15-94

Signed by Stephan J. Szyszkoski Date 10-5-1994  
Surveyor's Michigan License No. 33986

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

For the Michigan Department of Natural Resources - Forest Management Division.

244