

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Ontonagon County
Page 1 of 1
JEM Date 11/23/1999 Time 18:39:22
RECORDING FEE: 9.00

For corners in

Table with columns: Ontonagon County, Located in:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

SURVEY & REMONUMENTATION

MAR 23 2000

SECTION

Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 1-13. Contains numbers 1-36 representing section numbers.

I, Joseph C. Domitrovich, in a field survey on November 5, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M - 6 & A - 6) 1/4 Corner common to Section 13, T51N, R40W and Section 18, T51N, R39W.

1845 Austin Burt set a post with ties:

Table with 3 columns: Tie description, Bearing, Distance. Includes 12" Sugar S 40°E 24 links and 14" Sugar N 82°W 33 links.

No Record of Subsequent Restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found no remains of the original corner or accessories. I did find a 16" Hard Maple that was blazed on 4 sides and painted "APPR 1/4". This tree falls 76' East of a line between Section Corners and 28' South of a split. I did not accept the blazed maple as the corner. I re-established a position for the 1/4 Corner by single proportionate measurement between the 1/4 corner one mile North and section corner 1/2 mile South.

Research on file with County Remonumentation Representative.

NEER GROUP APPROVED
Earl W. Applebaum
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 2 1/2" x 30" aluminum pipe with a 3" diameter aluminum cap stamped to read: County Remonumentation; T51N, R40W, R39W; 1/4; S. 13, S. 18; 1999; P.S. 37273. Corner falls on top a narrow ridge which slopes west to a grassy swamp and east to a small low area. Corner falls 106' south of an E - W trail. Ties:

Table with 3 columns: Witness object, Bearing, Distance. Includes 5" Hard Maple S 45°E 9.79', 3" Hard Maple S 30°W 12.73', 11" Soft Maple S 83°W 11.46', 8" Hard Maple N 10°E 4.92', Steel Sign Rail East 0.95' (to face), NE Corner Section 13 N 00°33'27"W 2661.16', SE Corner Section 13 S 00°33'27"E 2661.16'.



NOTE: Bearings to witness objects are magnetic. Distances are to a nail in side of the witness object unless noted.

Signed by [Signature]

Date 11/09/99

Surveyor's Michigan License No. 37273