

*Final*

✓

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 51 N.R. 41W


Ontonagon COUNTY

DESCRIPTION OF CORNER Center Corner, Section 8.

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 5/8/67

WITNESSES TO CORNER..... 7" W. Spruce (BT) S55°W 13.3'



7" W. Spruce (BT) S44°E 23.5'

AND

CIRCLE CORNER REGISTERED

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This Corner established on line between the East and the West Quarter Corners.

Corner lies 1/2 chain West of plantation edge and in the spruce planting.

Corner co-ordinates are; N. 58622.4 E. 39894.5 of the W. Pine Co-ordinate System.

**SURVEYOR'S SEAL**

*Billy D. Buckler*

SIGNED Billy D. Buckler DATE 2/28/68  
REGISTERED LAND SURVEYOR