

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>42W</u>	<u>M-5</u>
	T <u>51N</u> R <u>41W</u>	<u>A-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**SURVEY &
 REMONUMENTATION**

MAY 22 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

The section corner common to Sections 12, 13, 7, 18, T51N-R42W-R41W.

I, John R. Garske, in a field survey on July 23, 19 96
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current
 manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and
 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a
 Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found
 as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- In 1845, Austin Burt, U.S. Deputy Surveyor, set a post with the following bearing trees:
 8" Birch - S62°W - 35 links
 10" DO - N34°W - 18 links
- 1966± Era MDOT Plans show corner 7.39 feet west of the curved centerline of Highway 64.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found a 3/4" diameter iron rod in an M.D.O.T. Monument Box which matches the location shown on the highway plans. The corner location matches stationing shown and our distances to corners with the plans. This corner has been used and accepted in many surveys of record, including a 1981 survey by William Innich, R.L.S.

Record research on file.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I established the following reference objects:
 2 1/2" aluminum pipe with 3 1/4" aluminum cap stamped: T51N, R42W, R41W, R.M., S-12, S-7, S-13, S-18, 1996,
 R.L.S. 28410, N51°E, 53.76 feet with a steel sign rail 1.09 feet away.
 Another cap stamped the same as above except S55°E - 50.50 feet with a steel sign rail 1.31 feet away.
 Power Pole - S54°E - 77.79 feet

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE 8-14-96

SEE SKETCH ON BACK

Signed by John R. Garske Date 8-11-96
 Surveyor's Michigan License No. 28410