

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T51N R 41W	<u>A-9</u>
	T51N R 42W	<u>M-9</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

SURVEY &
 REMONUMENTATION

JAN 11 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
 Section Corner common to Sections 19 & 30, T51N R41W
 & Sections 24 & 25, T51N R42W.

I, Earl W. Applekamp, in a field survey on March 23, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 Original corner established by Austin Burt, U.S. Deputy Surveyor, August 1845. Set Wood Post on left bank of Mineral River.

ORIGINAL BEARING TREES:
 18" Lynn N50°W 3.30 feet
 8" Sugar N53°E 17.16 feet

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 5-13-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 No original evidence was found. At the apparent Corner position the Mineral River is making a "U" bend and has eroded the bank North along the Section line. MDOT Highway drawings dated 1956 indicate corner falls in River and a post was set 10.8 feet North of corner. This was not found. Using information on highway drawing I re-established the corner and it falls in the river. This location is in conformance with original field note distances to corners North and South. I re-established the corner as shown in "C" below.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 I set a reference monument N00°-03'-49"E, along the section line from the true corner position. The monument is a 2½"X30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T51N, R41W, R42W, S19, S30, S24, S25, 1998, P.S. 17610, J.M., S00°-03'-49"W. This monument is tied in with 3 bearing trees and a reference object.

Nail in 5" Maple N88°W 30.52' - Nail in Y. Birch S35°E 6.94'
 Nail in 8" Maple N35°E 34.22' - 6' Steel Sign Post Due South 0.98'
 Additional Witness Monument, N00°-03'-49"E, along the Section line 108.18 feet from the true corner position.



Signed by Earl W. Applekamp Date March 27, 1998
 Surveyor's Michigan License No. 17610