

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON (County)	Located in:	Corner Code #
1. Public Land Survey	T51N R41W	A-10
	T51N R42W	M-10
	T___ R___	_____
	T___ R___	_____
2. Property Controlling In Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

SURVEY &
 REMONUMENTATION

JAN 11 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

$\frac{1}{4}$ Corner common to Sections 25 & 30, T51N R41W & T51N R42W.

I, Earl W. Applekamp, in a field survey on March 25, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor, August 1845. Set Wood Post.

ORIGINAL BEARING TREES:

10" Hemlock	S47°E	5.94 feet
12" Sugar	N60°W	7.92 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Corner position is in a large clear-cut area logged 3-4 years ago. Corner was re-established by single proportionate measure on line between opposite section corners North & South.

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY REPRESENTATIVE
 5-13-98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/4" X 30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, $\frac{1}{4}$, T51N, R41W, R42W, S25, S30, 1998, P.S. 17610. I established three bearing trees and a reference object.

Nail in 3" Y. Birch	N38°W	89.00'	-	Nail in 2" Y. Birch	S50°W	20.92'
Nail in 2" Maple	S68°E	30.05'	-	6' Steel Sign Post,	Due South	1.08'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date March 27, 1998