

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 51N R 41W	<u>A-13</u>
	T 51N R 42W	<u>M-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

JUN 11 1998

SECTION

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Section Corner common to S31, T51N R41W & S36,  
 T51N R42W on the Fifth Correction Line.

I, Earl W. Applekamp in a field survey on May 21, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by William A. Burt, U.S. Deputy Surveyor, August 29, 1845. Set wood post.

ORIGINAL BEARING TREES:

14" Hemlock	N37°E	11.22 feet
8" Sugar	N18°W	19.14 feet

**PEER GROUP APPROVED**  
*Earl W. Applekamp*  
 COUNTY REGISTERED

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence remains. This area had been cleared for the Copper Range Co. copper plant in 1952. The location of this corner was tied to the Copper Range coordinate system when the area was cleared. Corner was re-established at these coordinates. The location of the corner has a coordinate of N-34935.71 and E-31632.61 Copper Range Coordinate system data. This corner is on the Fifth Correction Line.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2½"x30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T51N, R41W, R42W, S31, S36, 1998, P.S. 17610. I established 5 bearing objects.

NE Cor. Conc. wall P. Plant,	S47°-32'-43"E,	14.44 feet
NW Cor. Conc. wall P. Plant,	N78°-30'-21"W,	58.20 feet
SW Cor. Conc. Electrical Pull Box,	N06°-57'-32"E,	149.28 feet
6 Foot Steel Sign Post,	West	1.31 feet
6 Foot Steel Sign Post,	East	1.45 feet



Signed by Earl W. Applekamp  
 Surveyor's Michigan License No. 17610

Date June 2, 1998