

JUDITH D. ROEHM 1P  
Ontonagon County

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970 of 1 LC 5/ 63  
Ontonagon County Remonumentation Corner Rec. Date 05/26/98 Time 10:45

For corners in

Ontonagon County	Located in:	Corner Code #
1. Public Land Survey	T51N R41W	K-5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

RECORDING FEE: 9.00

JUDITH D. ROEHM 1P  
Ontonagon County  
Page 1 of 1 LC 5/ 63  
JDR Rec. Date 05/26/98 Time 10:45  
RECORDING FEE: 9.00

SURVEY &  
REMONUMENTATION

JAN 11 1999

SECTION

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Joseph C. Domitrovich, in a field survey on March 6, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner of Sections 11, 12, 13 and 14, T51N, R41W

1846- S.W. Higgins set a post: 15' Hemlock N50°E 28 links  
42' Sugar S35°W 50 links

I found no other record of subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

The original corner and accessories have been destroyed by farming and logging activity since the turn of the century. In the area of the corner I found the remains of an old homestead clearing, a very old North-South fence and extensive clearcut logging to all sides. Distances between ¼ corners and Section corners in this section are very long and distances measured to existing streams vary considerably from record GLO calls. I believe this is the result of either gross error or fraudulent work on the part of the original Government Surveyor.

I reestablished the corner position by proportionate measurement, holding the old North-South Fence for the Departure and a position midway and on line between ¼ corners to the north and south for the Latitude. I believe the position I have placed the corner at to be the best and most equitable position for the corner and have monumented it as such.

Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 5/8" x 24" iron pin driven into the old North-South fenceline with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; T51N, R41W; S.11, S.12, S.13, S.14; 1998; P.S. 37273.

Witnesses:

4" Hemlock	N44°E	31.65'
Steel Sign Post	East	1.41' (to face)
5" Poplar	S11°W	8.92'
5" Poplar	N42°W	3.87'
W1/4 Cor Sec. 12	N00°54'29"E	2786.20'
N1/4 Cor. Sec. 13	S88°30'26"E	2805.92'
W1/4 Cor. Sec. 13	S01°08'33"E	2786.94'

PEER GROUP APPROVED

*Paul W. Appleton*  
COUNTY REMONUMENTATION  
5-13-98



NOTE: Bearings are magnetic. Distances are to a nail in side of the witness object unless noted.

Signed by Joseph C. Domitrovich

Date 5/13/98

Surveyor's Michigan License No. 37273

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 26, 1871  
REVISED MAY 14, 1875  
REVISED JAN., 1883  
REVISED OCT., 1995