

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Ontonagon Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey	T <u>51N</u> R <u>41W</u>	<u>L-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

SURVEY & REMONUMENTATION

MAY 22 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

One-quarter section corner common to Sections 12, 13, T51N, R41W.

I, John R. Garske, in a field survey on July 17, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

In April 1846, S.W. Higgins, U.S. Deputy Surveyor, set a post with the following bearing trees:
 36" Y. birch - N30°E - 18 links
 10" DO - S65°W - 10 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I established the corner location at the centerline of Halfway Road opposite an ancient fence running east. Measurements to corner positions east and south were used to verify this position.

Record research on file.

PEER GROUP APPROVED
Earl W. Applebury
 COUNTY REPRESENTATIVE 8-14-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 3" stainless steel spike in the pavement and established the following bearing trees and/or reference objects:
 2 1/2" x 30" aluminum pipe with 3 1/4" aluminum cap stamped: County Remonumentation, R.M., S-12, S-13, 1/4, 1996, R.L.S. 28410, S44°W, 37.98' with a steel sign rail 1.04 feet away.
 Another was stamped the same as above except N39°W, 55.18' with a steel sign rail 1.06 feet away.
 Bearing Trees:
 11" maple in clump of 3B16 and 6 small - S42°W - 34.96 feet
 9" maple in clump of 3B16 - N78°W - 18.78 feet

- SEE SKETCH ON BACK -

Signed by *John R. Garske*
 Surveyor's Michigan License No. 28410

Date 14 No 96

