

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|---------------------------------------|-----------------------------|---------------|
| <u>ONTONAGON</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>51</u> N R <u>42</u> W | <u>K-5</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

SURVEY &
 REMONUMENTATION
 JAN 11 1999
 SECTION
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner common to Sections 11, 12, 13 & 14, T51N R42W.

I, Earl W. Applekamp, in a field survey on March 18, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | | |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor, Summer of 1846. Set Wood Post.

ORIGINAL BEARING TREES:

24" Hemlock S30°W 23.10 feet
 Hemlock 14" N25°E 13.86 feet

PEER GROUP APPROVED
Earl W. Applekamp
 COUNTY SURVEYOR
 5-13-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. At the corner position I found a 1½" pipe projecting 30" above ground. Numerous surveys have been performed in the area. All make reference to the pipe. I accepted the pipe as being the only logical position for the corner. I sawed the pipe off so it projected 6" above the ground and set a 30" aluminum pipe over it as described below.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2½"x30" split base aluminum pipe with a 3" cap over the 1½" steel pipe. The cap is stamped to read: County Remonumentation, T51N R42W, S11, S12, S13, S14, 1998, P.S. 17610. I established three bearing trees and a reference object.

5" Yellow Birch N44°W 9.66' - 5" Soft Maple S21°E 26.60'
 7" Soft Maple N74°E 13.48' - 6' Steel Sign Post S23°W 1.54'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date March 23, 1998