

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON (County)	Located In:	Corner Code #
1. Public Land Survey	T 51NR 42W	K-8
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

SURVEYING
 REMONUMENTATION

JAN 11 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

¼ Corner common to Sections 23 & 24, T51N R42W.

I, Earl W. Applekamp, in a field survey on June 08, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by S.W. Higgins, U.S. Deputy Surveyor, summer of 1846. Set Wood Post.

ORIGINAL BEARING TREES:

24" Hemlock N85°W 6.60 feet
 30" Hemlock S20°E 9.24 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. No other evidence of anyone marking the corner were found. I re-established the corner by single proportionate measure and on line between opposite section corners, North & South.

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVAL

Earl W. Applekamp
 COUNTY REPRESENTATIVE 6-17-98



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2½"X30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T51N, R42W, ¼, S23, S24, 1998, P.S. 17610. I established 3 bearing trees and a reference object.

Nail in 9" Y. Birch S60°W 33.91' - Nail in 5½" Hard Maple S02°E 42.28'
 Nail in 9" Soft Maple N24°W 21.83' - 6' Steel Sign Post East 0.84'

Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date June 12, 1998