

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T51N R42W	K-11
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

SURVEY &
 REMONUMENTATION

JAN 11 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Section Corner common to Sections 25, 26, 35 & 36, T51N R42W.

I, Earl W. Applekamp, in a field survey on April 10, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original Corner established by S.W. Higgins, U.S. Deputy Surveyor, summer of 1846. Set wood post.

ORIGINAL BEARING TREES:

11" Hemlock N10°W 19.80 feet
 8" Ironwood S35°E 8.58 feet

FEES GROUP APPROVED
Earl W. Applekamp
 COUNTY REGISTERED 5-13-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original or other evidence was found. The corner position falls in a clear cut area. The original survey calls for a small stream 1.4 chains East and the same stream 6 chains North. Using this position and a position based on a traverse from the SW Corner, Section 4, T50N R42W, North along Highway M-64 to Lake Superior and back South on the West side of the Big Iron River to the SW Corner Section 36, T51N R42W tying in all the existing corner evidence. The calculated position based on the traverse was in conformance with the original field calls. Corner was set using the original field note calls.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2½"X30" split base aluminum pipe, with a 3" cap stamped to read: County Remonumentation, T51N, R42W, S25, S26, S35, S36, 1998, P.S. 17610. I established 3 bearing trees and a reference object.

Nail in 6" Maple N78°W 17.39' - Nail in 5" Maple S20°E 25.39'
 Nail in 6" Maple N08°E 9.84' - 6' Steel Sign Post Due East 0.80'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date May 12, 1998