

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON

(County)

Located in:

Corner Code #

1. Public Land Survey

T51N R42W

K-12

T R

T R

T R

2. Property Controlling
In Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1/4 Corner common to Sections 35 & 36, T51N R42W.

I, Earl W. Applekamp, in a field survey on June 10, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

JAN 15 1998

SECTION

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by S.W. Higgins, U.S. Deputy Surveyor, summer of 1846. Set Wood Post.

ORIGINAL BEARING TREES:

14" Hemlock	N15°E	5.94 feet
10" Hemlock	S25°W	11.88 feet

PEER GROUP APPROVAL

Earl W. Applekamp

COURT ESTABLISHED 6-17-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. I found a squared post and an old yellow tag S03°E, 50 feet from the calculated position of the corner. No record of this post is known. No surveys come from this post. It appeared it was placed by a cruiser in 1952. I could not accept this as the true corner position. A Creek call North was not in agreement, whereas using a calculated position it was in conformance. I re-established the corner by single proportionate measure and on line between opposite Section Corners North & South.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2"X30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T51N R42W, 1/4, S35, S36, 1998, P.S. 17610. I established 3 bearing trees and a reference object.

Nail in 10" Soft Maple	S17°E	44.29'	- Nail in 12" Hard Maple	N08°E	24.49'
Nail in 7" Hard Maple	N44°E	24.55'	- 6' Steel Sign Post	West	1.20'



Signed by Earl W. Applekamp

Surveyor's Michigan License No. 17610

Date June 12, 1998