

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON  
 (County)

Located In: Corner Code #

- |                                    |                                        |             |
|------------------------------------|----------------------------------------|-------------|
| 1. Public Land Survey              | T <u>51</u> N R <u>42</u> W            | <u>K-13</u> |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u>  |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u>  |
|                                    | T <u>   </u> R <u>   </u>              | <u>   </u>  |
| 2. Property Controlling In Section | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u>  |
|                                    | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u>  |
| 3. Miscellaneous Property In Sec.  | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u>  |
|                                    | S <u>   </u> T <u>   </u> R <u>   </u> | <u>   </u>  |

JUN 11 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Section Corner common to Sections 35 & 36 on the Fifth Correction Line.

I, Earl W. Applekamp, in a field survey on May 27, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor, August 30, 1845. Set wood post.

ORIGINAL BEARING TREES:

- |             |       |            |
|-------------|-------|------------|
| 12" Hemlock | N38°E | 13.20 feet |
| 16" Hemlock | N47°W | 19.14 feet |

PEER GROUP APPROVED  
*Earl W. Applekamp*  
 COUNTY REGISTERED 6-17-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence could be found. At the corner position I found an old Hemlock post and a squared Cedar post. Both were rotted off and laying on the ground. There were 3 blazed trees pointing to this position. In the Copper Range Company records I found a coordinate for the corner. I ran a traverse to the Copper Range Coordinate position. This is where the old posts were. I re-established the corner at the Copper Range Coordinate. This position is in conformance with the original field note call to the Big Iron River.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2" x 30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T51N R42W, S35, S36, 1998, P.S. 17610. I established 3 bearing trees and a bearing object.

- |            |       |        |   |                          |            |       |
|------------|-------|--------|---|--------------------------|------------|-------|
| 8" Maple   | N30°E | 24.37' | - | 6' Steel Sign Post       | West       | 0.97' |
| 9" Hemlock | N82°E | 26.16' | - | Copper Range Coordinates | for Corner |       |
| 9" Maple   | S20°W | 37.37' | - | N 34954.69               |            |       |
|            |       |        | - | E 26385.43               |            |       |



Signed by Earl W. Applekamp  
 Surveyor's Michigan License No. 17610

Date June 2, 1998