

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>42W</u>	<u>L-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**SURVEY &
 REMONUMENTATION**

MAY 22 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

One-quarter section corner common to Sections 12 and 13, T51N, R41W.

I, John R. Garske, in a field survey on July 23, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original township survey by Austin Burt, U.S. Deputy Surveyor, August-September 1845. Original township subdivision by S.W. Higgins and Bela Hubbard, U.S. Deputy Surveyor, 1846, set:

- 1/4 post
- 12" Hemlock - N50°W - 18 links (11.88 feet)
- 20" Y. birch - south - 20 links (13.2 feet)

In May 1992, John R. Garske, R.L.S. 28410 re-established the corner and set 2 inch diameter iron pipe 3 feet long with the following bearing trees and reference objects were established:

- 5/8" rebar - N55°E - 8.80 feet
- 3/8" rebar - S2°-30'W - 7.65 feet
- 4" Y. birch - S15°E - 12.81 feet
- 4" Aspen stump - N12°W - 0.70 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I originally set the corner in 1992 by single proportion after failing to find any evidence. I found my accessories from 1992 and brought it up to State and County specifications as noted below.


P.A. 74 research on file.

PEER GROUP APPROVED
Earl W. Applekamp 8-14-96
 COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 3/4" x 36" aluminum rod with a 3" aluminum cap inside the iron pipe found and grouted with concrete stamped: T51N-R42W, 1/4, S-12, S-13, 1996, R.L.S. 28410. The following bearing trees and reference objects were established:

- Steel sign rail - N57°W - 1.55 feet
- 3 1/2" Y. birch (exist) - S15°E - 12.87 feet
- 3/4" rebar (exist) - S2°-30'W - 7.62 feet
- 5/8" rebar (exist) - N55°E - 8.83 feet
- 4" aspen stump (exist) - N12°W - 0.69 feet (1.8' high)



Signed by John R. Garske
 Surveyor's Michigan License No. 28410

Date 8/19/96