

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ONTONAGON
 (County)

	Located In:	Corner Code #
1. Public Land Survey	T51NR 42W	L-13
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REGISTERED
 JAN 11 1998
 SECTION
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
 South 1/4 Corner, Section 36, 5th Correction line, T51N R42W.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Earl W. Applekamp, in a field survey on May 21, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Original corner established by Austin Burt, U.S. Deputy Surveyor, August 30, 1845. Set Wood Post.

ORIGINAL BEARING TREES:
 24" Hemlock N26°E 31.02 feet
 12" Maple N08°W 25.08 feet

FEES GROUP APPROVED
Earl W. Applekamp
 COUNTY REGISTER 6-17-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 No original evidence was found. Area is a Trailer Court and has been since 1953. In 1960 Victor Arcand RLS, # 10678, showed me a 1 1/2" pipe at the corner. This pipe was tied to the Copper Range Company Coordinate System. In 1972 I used this pipe to describe the Trailer Court, which was sold at this time. This survey is recorded in Liber 1, of surveys page 15. I accepted this pipe as being the corner and replaced it with a monument as described in "C". The corner has a value of N34935.33 & E28998.10 feet, Copper Range Coordinate System.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 At the corner position I set a 2 1/2"x30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T51N, R42W, 1/4, S36, 1998, P.S. 17610. I established 2 bearing trees and two reference objects.

Nail in 14" Hemlock N20°W 189.55' - Nail in Power Pole S62°W 52.99'
 Nail in 14" Hemlock N74°E 182.68' - 6' Steel Sign Post, South 0.75'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date June 11, 1998