

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T51N R41W	A-6
	T51N R42W	M-6
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

COURTNEY A.  
REMONUMENTATION

JAN 11 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

1/4 Corner common to Sections 13 & 18, T51N R41W & T51N R42W.

Earl W. Applekamp, in a field survey on March 26, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor, September 1845. Set Wood Post.

ORIGINAL BEARING TREES:

8" Fir S70°E 2.97 feet  
 16" Sugar N15°W 23.76 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Corner falls in the paved area of Michigan Highway M-64. Corner was re-established by single proportionate measure and on line between opposite section corners North & South.

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVED  
*Earl W. Applekamp*  
 5-13-98 COURT REPRESENTATIVE



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a R.R. Spike in the Northbound lane of Michigan Highway M-64. The corner is 10.8 feet East of the Highway center-line. I established two reference monuments and two bearing objects. Reference monuments are 2 1/2" X 30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T51N, R41W, R42W, 1/4, R.M., S13, S18, 1998, P.S. 17610.

REF. MON. N67°-22'-42"W 61.66' - Nail in 6" Ash S81°-10'-47"W 60.25'  
 REF. MON. N85°-15'-54"E 94.82' - Center-line M-64 Due West 10.8'

Signed by Earl W. Applekamp  
 Surveyor's Michigan License No. 17610

Date March 27, 1998