

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>ONTONAGON</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T51NR 41W	A-12
	T51NR 42W	M-12
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

1/4 Corner common to Sections 31 & 36, T51N R41W & R42W.

I, Earl W. Applekamp, in a field survey on May 22, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Austin Burt, U.S. Deputy Surveyor, summer of 1845. Set wood post.

ORIGINAL BEARING TREES:

6" Black Ash S62°E 21.12 feet
 10" Black Ash N13°W 20.46 feet

PEER GROUP APPROVAL
Earl W. Applekamp
 COUNTY REGISTER
 6-17-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Area was completely cleared in 1970 for the base of a huge crushed slag pile. Part of the slag pile has been removed allowing the corner to be set in its proper position. The corner was re-established by single proportionate measure and on line between opposite section corners North & South.

Research on file with the Ontonagon County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2" X 30" split base aluminum pipe with a 3" cap stamped to read: County Remonumentation, T51N, R41W, R42W, 1/4, S31, S36, 1998, P.S. 17610. I established 3 bearing trees and two reference objects.

Nail in 3 1/2" Aspen N20°E 420.10' - Nail in 3" Aspen S24°E 274.27'
 Nail in 4" Aspen N32°E 484.82' - 6' Steel Sign Post West 1.65'
 - 6' Steel Sign Post East 1.65'



Signed by Earl W. Applekamp
 Surveyor's Michigan License No. 17610

Date June 2, 1998