

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>52</u> N. <u>8.</u> , R. <u>37</u> <u>W.</u>	<u>I 13, H 13, J 13</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. _____, S., R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____, S., R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

a. Description of original monument and accessories and/or subsequent restoration:

- Corner I 13: Original monument and accessories not found.
Found 1" I.D. iron pipe 3 ft. above ground.
Original bearing tree sighted by W. Waara May 5, 1944.
- Corner H 13: Original monument and accessories not found.
Found 1" I.D. iron pipe 3 ft. above ground.
- Corner J 13: Original monument and accessories not found.
Found 1" I.D. iron pipe 3 ft. above ground.

b. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner I 13: Re-established 5-11-76 at iron pipe.
- Corner H 13: Re-established 5-11-76 at iron pipe. Pipe has been used as corner for many years. Fits good with other corners in area.
- Corner J 13: Re-established 5-13-76 at iron pipe. Has been used as corner for many years. Fits good with other corners and stream east.

c. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner I 13: 1" I.D. iron pipe 3 ft. above ground.
10" Sugar N68°W 20.9 ft. S34, NBT
8" Sugar N73°E 27.4 ft. S35, NBT
- Corner H 13: 1" I.D. iron pipe 3 ft. above ground.
6" Sugar N59°E 15.6 ft. S, NBT
6" Sugar N59°W 20.0 ft. S, NBT
- Corner J 13: 1" I.D. iron pipe 3 ft. above ground.
12" Spruce N32°W 32.4 ft. S, NBT
Sugar S58°W 22.6 ft. S, NBT


SIGNED BY _____ DATE _____

SURVEYORS MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE June 28, 1976
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006