

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>52</u> N. S., R. <u>37</u> E. W.	<u>G13, K13, M13</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration: x 48"
- Corner G13: Original monument and accessories not found. Found 1" I.D. iron pipe.
 - Corner K13: Original monument and accessories not found. Found 1" I.D. iron pipe 30" above ground.
 - Corner M13: Original monument and accessories not found. Found 2" O.D. iron pipe 3 ft. above ground.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner G13: Re-established 5-18-76 at location of iron pipe. Has been used as corner for many years. Fits good with other corners in area.
 - Corner K13: Re-established 5-18-76 at location of iron pipe. Has been used as corner for many years. Fits with other corners in area.
 - Corner M13: Re-established 6-8-76 at location of iron pipe. Has been used as corner for many years. Fits good with other corners in area, and fits with swamp edge west.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner G13: Set 1" I.D. x 36" iron pipe with aluminum cap.(4").
 - 9" Sugar N77°W 15.9 ft. S33, NBT
 - 10" Sugar N22°E 30.3 ft. S34, NBT
 - Power Pole S11°E 43.0 ft.
 - Corner K13: 1" I.D. iron pipe 30" above ground.
 - 9" Maple N50°W 44.8 ft. S35, NBT
 - 10" Maple N17°E 35.3 ft. S36, NBT
 - Power Pole S35°W 44.4 ft. S5
 - Corner M13: 2" O.D. iron pipe 3 ft. above ground.
 - 5" Spruce S13°W 19.2 ft. S36, NBT
 - 4" Spruce S30°E 35.2 ft. S 6, NBT
 - Power Pole #158 N12°W 44.6 ft. S1


SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE June 28, 1976
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006