

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

T Ontonagon
(County)

Located In:

Corner Code -##

1. Public Land Survey	T	52N	R	37W	E11
	T		R		F11
	T		R		G11
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, **Keith Sackett**, in a field survey on **April 23**, 19**92**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	14	15	16	17	18						
7												
8	19	20	21	22	23	24						
9												
10	25	26	27	28	29	30						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:


E11 Original monument and accessories not found. Found 1" ID pipe, old post, Forest Service and Keweenaw Land Assoc. location posters.	F11 Original monument and accessories not found. Found 1 1/2" ID pipe, Vulcan location poster.	G11 Original monument and accessories not found. Found 1" ID pipe, Vulcan location poster.
--	--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E11 Found 1" ID pipe, old post, Forest Service location poster dated 1946 and Keweenaw Land Assoc. poster, all fit well with other corners in the area.	F11 Found 1 1/2" ID pipe and Vulcan location post which fits well with other corners in the area.	G11 Found 1" ID pipe and post and Vulcan location poster which fits well with other corners in the area.
---	---	--

C. Description of monument for corner and accessories established to perpetuate localing the position of the corner:

E11 Found 1" ID pipe, old post, Forest Service and Keweenaw Land Assoc. location posters. 9" yellow birch S27W 8.4' S32 NBT/Keweenaw Land Assoc. poster. 4" maple S20E 16.6' S33 NBT 4" sugar N33W 16.6' S29 NBT 5" bealock N72E 21.5' S28 NBT	F11 Found 1 1/2" ID pipe and Vulcan location poster. 7" bealock S42W 12.5' 1/4s NBT 8" ironwood S42E 9.6' 1/4s NBT 12" sugar N64W 28.4' 1/4s NBT/Vulcan location poster 4" ironwood N53E 23.0' 1/4s NBT	G11 Found 1" ID pipe and post and Vulcan location poster. 12" sugar N22W 0.7' S28 NBT/Vulcan poster 4" sugar N47E 9.2' S27 NBT 5" sugar S20E 14.2' S34 NBT 12" yellow birch S29W 13.6' S33 NBT
--	---	--



Signed by

Keith Sackett

Date

April 24, 1992

Surveyor's Michigan License No.

19006