

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 Ontonagon

(County)

Located In:	Corner Code #
T <u>52N</u> R <u>37W</u>	<u>M7</u>
T <u>52N</u> R <u>37W</u>	<u>M6</u>
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

M6 October 12, 1995

I, Stephan J. Szyszkoski, in a field survey on M7 October 18, 1995, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13	12	11	10	9	8	7	6
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

A. Description of original monument and accessories and/or subsequent restoration:

(M7) Corner common to Sections 18-19 T52N-R36W and Sections 13-24 T52N-R37W. Corner established in 1845 by Wm. A. Burt. "80.00 Corner of Sections 13&24 and set post. Sugar 10 S39W 61, do 12 N37W 28". Corner noted in Mead records as 1 1/2" iron pipe found January 24, 1966 with the following witnesses: 7" Elm (C&M tag) 7" Hard Maple (Yellow tag). Found no subsequent record.

(M6) Quarter corner common to Section 18 T52N-R36W and Section 13 T52N-R37W. Established in 1845 by Wm. A. Burt: "40.00 Set qr Section post. Hemlock 12 S27W 37, do 16 N30W 28". Mead records dated Jan 24, 1966 state: 4" Ash post at corner Old Hemlock stump (B.T.) N26W 17 ft., 8" Hard Maple (Beaver) S24W 9 ft". Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M7) Original post and accessories not recovered. Recovered a 1 1/2" iron pipe with 8" Sugar Maple and yellow Vulcan tag facing. The 7" elm with C&M tag noted in 1966 is dead and has recently fallen. Distance north 1/2 mile to probable original 1/4 corner and 1 mile to original section corner check reasonably well with the original record. I accepted the pipe as the best available evidence of the position of the original corner. Left the pipe in place and marked 4 witnesses as described below.

(M6) Original post not recovered. Mead's Ash post was not recovered. Re-monumented the corner at record bearing and distance from the remains of the original bearing trees. The Hemlock NW was recovered as a rotted stump of proper size and species. No markings were found. A distinct stump hole marks the location of the other Hemlock BT. The corner is also in accord with Mead's 8" Maple, recovered as described. Also, An old unreadable location poster, possibly by Copper Range, faces the corner on a 14" Sugar. A dead 4" squared Sugar was found adjacent. Distances North and South to adjacent Section corners are -0.06 ch. and +0.32 ch. respectively, compared to the original record. At the position for the corner, I placed a 1" I.O.x36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M7) Found 1 1/2" iron pipe.
 Blazed and scribed the following new bearing trees:

9" Sugar found with Vulcan tag
 S18W 7.0' "S24 NBT"
 5" Sugar S48E 21.1' "S19 NBT"
 10" Sugar N42E 20.9' "S18 NBT"
 12" Sugar N19W 26.4' "S13 NBT"
 Bearings are magnetic.

(M6) Set 1" pipe with 4" MDNR cap.
 Blazed and scribed the following new bearing trees:

14" Sugar N08W 26.6' "1/4S NBT"
 15" Maple N47E 10.1' "1/4S NBT"
 10" Sugar S20E 3.7' "1/4S NBT"
 8" Sugar N80W 17.6' "1/4S NBT"
 Bearings are magnetic. Placed a 3" squared ash post adjacent.



Signed by Stephan J. Szyszkoski Date 10-26-95
 Surveyor's Michigan License No. 33986