

9.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ontonagon

(County)	Located In:	Corner Code ≠
1. Public Land Survey	T 52N R 37W	M8
	T 52N R 37W	M5
	T R	
	T R	
2. Property Controlling In Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Stephen J. Szyszkoski, in a field survey on September 14, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(M8) Quarter corner common to Section 24 T52N-R37W and Section 19 T52N-R36W. Corner reestablished in 1964 by Billy D. Buckler by single proportionate measurement between section corner 1/2 mile north and quarter corner 1 mile south. Corner marked by a wood post and the following NBTs: 14" H. Maple South 83 links, 9" H. Maple N72W 07 links, 11" H. Maple N67E 45 links. Mead records state "Corner destroyed by tractor skidding February 11, 1966".

(M5) Section corner common to Sections 12-13 T52N-R37W, and Sections 7-18, T52N-R36. Corner established in 1845 by Deputy Surveyor Wm. A. Burt as follows: 1) Set post, 2) Birch 10 S75W 4, 3) Birch 12 N50E 43, subsequent bearing trees established during section subdivision: 4) Y. Birch 10 N60W 27, 5) Elm 14 S18E 39. Line notes show: 6) North 1.50 Stream 6 c. NW, Notes from Mead, dated March 1945 state corner is a 8" squared maple with 18" Birch (stub) B.T. bearing N53E 27', 18" birch (M.C.L.) S15W, 24" Birch (old blazes) N75W 24', Names on 26" Elm S80E 30', "corner is in the bottom of a steep side hill facing east about 1/2 ch. W. f a small creek".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M8) Buckler's wood post not recovered. Restored the corner at record distance from the three 1964 NBTs as follows: 1) 18" Sugar stump, recently cut, with old base blaze, S64W 41.8', 2) N72E 12" Sugar with old blazes 29.7', 3) N71W 12" Sugar with old blazes 4.6'. At the position for the corner, I placed a 1"x32" iron pipe, capped with a 4" dia. cast aluminum MDNR tablet. Marked two new bearing trees as described below.

(M5) Original post not recovered. Recovered 16" Sugar with old blazes on 4 sides-the 1945 8" squared maple- S53W 27' from the rotted remains of an old stump, the stub B.T. in Mead's notes. Restored the corner from the original record as referenced above: 1) not recovered, 2) Found remains of Birch stump bottom, root holes, and overturned, rotted bole, which had fallen downhill, at record bearing and distance, believed to be original B.T. 3) found rotted stump approx. 18" dia. at record bearing and distance (the stub B.T. noted in 1945), 4) found rotted Y. Birch stump approx. 24" dia. (no iron marks discernable) at record bearing and distance, believed to be original B.T. 5) no trace, 6) meas. 120' to small stream. No trace of 26" elm noted in 1945, believe the 24" Birch noted in 1945 to be original B.T. N60W, and noted at 4) above. At the position for the corner, I placed a 1"x32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet. From the corner monumented, the squared maple noted in 1945 bears N66E, 2.7'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M8) Set 1" pipe with a 4" MDNR cap.
Blazed and scribed the following new bearing trees:
5" Sugar S26W 23.6' "S24 NBT"
9" Sugar N16E 25.4' "S19 NBT"
placed a squared 2" sugar post adjacent

(M5) Set 1" pipe with a 4" MDNR cap.
Blazed and scribed the following new bearing trees:
12" Sugar N44W 14.0' "S12 NBT"
16" Sugar N66E 2.7' "S7 NBT"
14" Y. Birch S40E 49.7' "S18 NBT"
2" Ironwood S20W 8.3' "X NBT"



Signed by Stephen J. Szyszkoski

Date 9-16-93

Surveyor's Michigan License No. 33986