

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Ontonagon (County)	Located In:	Corner Code #
1. Public Land Survey	T 51N R 40W	17
	T R	
	T R	
	T R	
2. Property Controlling In Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Recorded December 19 1994
at 2:30 o'clock P. M. in
Lib. Survey 3 page 242
Julia M. Haden, deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3	14	15	16	17	18	19	20	21	22	23	24	25	26
4	27	28	29	30	31	32	33	34	35	36	37	38	39
5	40	41	42	43	44	45	46	47	48	49	50	51	52
6	53	54	55	56	57	58	59	60	61	62	63	64	65
7	66	67	68	69	70	71	72	73	74	75	76	77	78
8	79	80	81	82	83	84	85	86	87	88	89	90	91
9	92	93	94	95	96	97	98	99	100	101	102	103	104
10	105	106	107	108	109	110	111	112	113	114	115	116	117
11	118	119	120	121	122	123	124	125	126	127	128	129	130
12	131	132	133	134	135	136	137	138	139	140	141	142	143
13	144	145	146	147	148	149	150	151	152	153	154	155	156

I, Stephan J. Szyzkoski, in a field survey on September 01, 1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Section common to Sections 14-15-22-23. Corner established in 1845 by Wm. A. Burt as follows: "Set Fir post cor of Secs. 14, 15, 22, 23. Cedar 12 S53E 17, Do 10 N74W 19." Distances to adjacent 1/4 corners east and south recorded by Burt as 40.02 ch. and 40.00 ch. respectively. Corner recorded pursuant to Act 74, 1970 by Keith L. Sackett for Michigan Dept. of Natural Resources in 1976 as follows: "Original monument and accessories not found. Re-established at location pointed out by local residents. Corner falls in center of gravel road in line with fence south and old road north. Corner fits good with other corners in the area. Set 1" I.D. x 24" iron pipe with 4" aluminum cap. Fence corner post S20W 30.4', Power pole N78E 134.1". Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original post and accessories have been destroyed by road and ditch construction and by cultivation. Original line call west from corner "1.50 Enter swamp C. N&S" is obliterated by same. Recovered and accepted the 1" I.D. x 24" iron pipe, anchored firmly in the road surface by a reinforcing rod cross-piece through the base, with only the stem of the aluminum cap remaining in the pipe. The cap itself was apparently sheared off by a plow or road grader. The pipe appears in good condition and is set vertically. The 1976 accessory power pole was found at record bearing (corrected for secular variation). The fence corner post was found at record bearing but 31.4' distant. I removed the stem of the aluminum cap, drove the pipe to 6" below the gravel surface, and firmly wedged into it a 2.5' length of 3/4" dia. aluminum rod, split at the bottom, capped with a 3/4" dia aluminum cap, center punched, and stamped to read "County Remonumentation T51N R40W 14 15 22 23, 9-1-94, PS 33986". I found the distances east and south to adjacent 1/4 corners remonumented in 1976 by Keith L. Sackett to be 39.934 ch. and 39.859 ch. respectively.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Drove capped aluminum rod described above into the 1976 1" I.D. iron pipe. Set nails with brass MONUMENT REFERENCE tags in the following (brgs magnetic):
7" Sugar S11E 47.63' mrd S23 N87
Power pole, unnumbered, N81W 236.36', nail is 5.5' above grnd.
Power pole, unnumbered, N82E 134.35', nail 4' above grnd.
6" cedar corner fence post S23W 31.32'.
Metal sign post S35E, 34.7'



**ONTONAGON COUNTY
PEER APPROVED**

Earl W. Wypkowsky
Ont Co Rep.
12-15-94

Signed by Stephan J. Szyzkoski Date 10-5-1994