

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ontonagon
(County)

Located in:

Corner Code --#

- 1. Public Land Survey T 51N R 40W 37
- T 51N R 40W K7
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Stephen J. Szyzowski, in a field survey on May 28, 1992, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	15	17	16	15	14	13							
7													
8	18	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(J7) Quarter corner common to sections 14-23, T51N-R40W. Corner previously recorded by Kieth L. Sackett in 1976 as monumented by a 1" I.D. x 24" pipe with a 4" aluminum cap and the following NBTs: 5' maple N12W 21.3' 1/4S NBT, 3' maple N22E 20.2' 1/4S NBT, 4" sugar S72E 26.5' 1/4S NBT.

(K7) Section corner common to sections 13-14-23-24. Corner previously recorded by Kieth L. Sackett in 1976 as monumented by a 1" I.D. x 24" iron pipe with a 4" aluminum cap and the following NBTs: 10" ash S58W 30.8' S23 NBT, 7' ash N02W 46.9' S14 NBT, Fence corner north, 22'. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J7) Recovered the stumps of the three NBTs noted above, all in proper relation, two with lower blaze, scribing, and notch visible. Monument placed in 1976 was not recovered. Placed a new monument, a 1" I.D. x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet at record bearing and distance from the remains of the 1976 NBTs. Marked four new witness trees as described below.

(K7) Monument placed in 1976 was not recovered. Placed a new monument, a 1" I.D. x 24" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, at record bearing a distance from the two 1976 NBTs and the fence corner, noted above. The 10" ash NBT is dead. Both were found standing, with scribing visible. Marked three new witness trees as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J7) Set 1" pipe with 4" MDNR cap. Blazed and scribed the following new bearing trees:
8" maple N15E 37.2' 1/4S NBT
9" maple S73W 33.3' 1/4S NBT
4" sugar S22E 27.0' 1/4S NBT
3" basswood S05W 18.2' 1/4S NBT

(K7) Set a 1" pipe with 4" MDNR cap. Marked the following new bearing trees:
5" basswood N24E 24.6' "S13 NBT"
3" R. Pine S62E 30.2' "S24 NBT"
5" basswood S58W 37.3' "S23 NBT"

Signed by Stephen J. Szyzowski Date 3-23-93

Surveyor's Michigan License No. 3398C