

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Ontonagon  
(County)

	Located in:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>40W</u>	<u>19</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	18	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on August 04, 1994, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(19) Section corner common to Sections 22-23-26-27. Corner recorded by Keith L. Sackett in 1976 as follows: "Reestablished 8-18-76 in center of county road east and west in line with fence north. Corner fits good with other corners in the area. Set 1" I.D. x 24" iron pipe with 4" aluminum cap in center of county road. 14' Elm S16N 48.4', 5' Aspen S35E 43.2', Fence corner post north, 35.1". Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(19) Recovered the 1976 monument. The cap of the monument had been broken off and the top of the pipe slightly bent. Straightened the pipe to it's original position and at record bearing and distance from the one remaining 1976 HBT, now an 11" Aspen in good condition. Marked two new bearing trees as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(19) Found 1" I.D. iron pipe with broken cap. Blazed and scribed the following new bearing trees:  
6" Maple S14N 68.7' "S27 HBT"  
8" R. Pine N12W 39.43' to a nail and MDNR ref. tag.  
Corner is in center of county road.  
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10-5-94  
Surveyor's Michigan License No. 33986