

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ontonagon
 (County)

Located In:

Corner Code #

1. Public Land Survey	T	<u>51N</u>	R	<u>40W</u>	<u>J9</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling In Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Sec.	S	_____	T	_____	R
	S	_____	T	_____	R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on September 01, 1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Quarter corner common to Sections 23-26. Corner established in 1845 by Wm A. Burt as follows: Set Hemlock post @r. Section corner. Hemlock 20 N60E 39, Cedar 12 N38W 14. Original record shows distances of 39.96 ch. east and west to adjacent section corners. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original post and accessories not recovered. The area in the vicinity of the corner as been severely disturbed by cultivation and road construction. Recovered the remains of an old wire fence line intersection 3.7' south and 2.9' west of the position proportionate to the original record. The fences extend east, west, and south from the intersection. The fence east extends the full 1/2 mile. The E'y quarter mile is all but obliterated. It travels a reasonably straight line and is noted in the record as having controlled the location of the reestablished X9 (recorded in 1976 pursuant to Act 74, P.A. 1970). The fence line east appears to follow an old road and exhibits a pronounced bow. The fence south is very old and in general, only the posts remain. Long-time area resident and adjacent land owner Henry Strauch reports these fence to have been in existence prior to his acquisition of the property, about 35 years ago, but has no further pertinent knowledge. I accepted the fence intersection as the best available evidence of the position of the original corner and monumented same. Found the distances west and east to monumented and previously recorded section corners to be 40.010 ch. and 40.097 ch. respectively.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed a 3/4" dia. x 48" long aluminum rod capped with a 3 1/4" dia. aluminum cap stamped to read "County
 Remonumentation T51N R40W 1/4 23-26, PS
 33986" from which bear the following:
 7" Maple N30E 38.83' arkd 1/4S NBT"
 7" Maple S53W 53.26' do
 4" Aspen N69W 5.54' do
 4" Aspen S62E 30.69' do
 A metal sign post North 1.0'. Distances
 are to nails with brass MDNR Reference
 tags. Bearings are magnetic.

Signed by Stephan J. Szyszkoski Date 10-5-1994
 Surveyor's Michigan License No. 33986



	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24	25			
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	32	33	34	35	36							
13													