

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Ontonagon

(County)

Located in:

Corner Code #

1. Public Land Survey

T 52N R 37W L12  
T 52N R 37W K9

T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

K9 Jan 29 2001  
L12 Jun 04 2001

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35				
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(L12) Center of Section 36. Not established in the original survey.

(K9) Corner common to Sections 23-24-25-26. 1846: S.W. Higgins set post. Sugar 12 N25W 19, Spruce 12 S80E 30. 1964: Billy D. Buckler found 1-1/4" ID iron pipe and "re-witnessed as set by unknown surveyor". 7" Hard Maple NE, 7" Hard Maple NW. Buckler says he measured 35.30 chains east to original Quarter corner.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(L12) Established the corner at the intersection of straight lines connecting opposite one-quarter corners.

(K9) Recovered a 1-1/4" iron pipe with 10" Sugar N51W 9.4' with double overgrown blazes facing. Measured 35.096 chains east to Buckler's monument at the quarter corner between 24 and 25. The NE'ly NBT was not recovered but it's stump may yet be in place, under the snow. I accept the pipe as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(L12) Set 1" IDx32" iron pipe with 4" alum. MDNR tablet. Blazed and scribed:

4" Sugar N13E 11.8' "C1/4 BT"  
4" Sugar S60E 3.2' do  
5" Sugar S47W 13.7' do  
12" Sugar N47W 15.8' do

Set sq'd cedar post adjacent. Bearings are magnetic. Distances to notch in lower blaze.

(K9) Found 1-1/4" iron pipe. Blazed and scribed:

10" Sugar N61E 10.1' "S24 NBT"  
6" Sugar S25W 21.1' "S26 NBT"  
6" Sugar N86W 23.8' "S23 NBT"

The 1964 wit. noted in part B.  
Sq'd cedar post adjacent. Bearings are magnetic. Distances to notch in lower blaze.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 9/25/01

For the Michigan Department of Natural Resources - Office of Property Management