

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ontonagon
 (County)

Located In:	Corner Code #
1. Public Land Survey	T 52N R 37W k7
	T 52N R 37W L13
	T R
	T R
2. Property Controlling in Section	S T R
	S T R
3. Miscellaneous Property in Sec.	S T R
	S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

L13 May 23 2001
 K7 May 21 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (K7) Corner common to Sections 13-14-23-24. 1846: Established by S.W. Higgins. Set post cor. Sec. 13.14.23.24. Elm 14 S50E 39, Lynn 16 N55W 47. 1964: Billy D. Buckler, RLS found iron pipe and measured roughly 75.02 chains east to section corner common to 13 & 24.
 (L13) South Quarter corner, Section 36. 1845: Established by M.A. Burt. ...40.00 Set qr. Section post. Cedar 18 N26E 25, Cedar 10 N62W 20.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K7) The original post and accessories were not recovered. Found a 1-1/2" ID iron pipe 36" in length, on the ground, with 4 blazed trees facing, and at the intersection of old blazed lines south, north, and west. Drove the pipe at this position. Measured 74.72 chains east to section corner. Accept the pipe as the best available evidence of the position of the original corner.
 (L13) The original post and accessories were not recovered, though there are a number of old cedar stumps in the area. Reestablished the corner on a line of mean true bearing between Section corners 2637.23' east and west, proportionate to the original record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K7) Reset 1-1/2" x 36" iron pipe. Blazed and scribed:	(L13) Set 1 IDx32" iron pipe with 4 alum. MDNR tablet. Blazed and scribed:
12" Y. Birch N04W 18.4' "S14 NBT"	10" Y. Birch N28E 11.0' "1/4S NBT"
9" Sugar S88E 27.5' "S24 NBT"	11" Cedar N52W 36.8' do
10" Sugar South 12.2' "S23 NBT"	8" Sugar N42W 8.2' do
6" Sugar N73W 6.1' "S14 NBT"	Northerly Power pole S51E 76.0' PK/tag
Bearings are magnetic. Distances to notch in lower blaze.	Set squared cedar post adjacent.
	Bearings are magnetic. Distances to notch in lower blaze of trees.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 9/25/01

For the Michigan Department of Natural Resources - Office of Property Management