

SURVEY & REMONUMENTATION

APR 26 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ONTONAGON
(County)

Located In: Corner Code ≠#

1. Public Land Survey	T <u>52</u> R <u>39</u>	M-3
	T <u>52N</u> R <u>38W</u>	(A-31) ✓
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Recorded November 16, 1994
at 1:20 o'clock P. M. III
Liber 3 Page 217
Julia Markley, Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section 1, 6, 7 & 12, T52N ³⁸R39-39W

I, Earl W. Applekamp, in a field survey on 09-06, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William A. Burt U.S. Deputy Surveyor, on September 12, 1845. Set Maple Post.

Original bearing trees:

Hemlock	12"	S09°E	19 Links	(12.54')
Hemlock	16"	S82°W	16 Links	(10.56')

ONTONAGON COUNTY
PEER APPROVED
Earl W. Applekamp
ONT. Co. REP.
9-14-94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" pipe near corner location. This did not agree with calls along the line from the original field notes. Corner was set by single proportionate measurement.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/4" aluminum pipe with a 3 1/2" Cap stamped to read: County Remonumentation, S-1, S-6, S-7, S-12, T52N R39 & 38W, 1994, P.S. 17610.

The following trees and objects were used to tie in the Corner:

12" Maple	N48°E	33.38 feet	-	11" Maple	S10°W	11.25 feet
10" Y Birch	S23°E	20.74 feet	-	Steel sign post	West	1.66 feet

Signed by Earl W. Applekamp Date November 11, 1994
Surveyor's Michigan License No. 17610

217