

SURVEY & REMONUMENTATION

APR 25 1995

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Ontonagon

(County)

Located In:

Corner Code #/

- | | | |
|---------------------------------------|---------------------------|---------------|
| 1. Public Land Survey S-30 | T <u>52N</u> R <u>39W</u> | <u>A-11</u> ✓ |
| | T _____ R _____ | _____ |
| | T <u>52N</u> R <u>40W</u> | <u>M-11</u> |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

RECORDED August 31 1994
 at 2:05 o'clock P. M. in
 Liber 3 page 203
Julie Masley Deputy
 Registrar of Deeds

Register of Deeds Stamp & File Number

I, John R. Garske, in a field survey on July 25, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

August 26, 1845 - William A. Burt, U.S. Deputy Surveyor - Set post:
 Sugar 9" - N30°E, 11 links (7.26')
 Y. birch 12" - N36°W, 16 links (10.56')

Various plats in Ontonagon refer to section corner.

1966 - State Highway project plans show corner location at intersection of U.S. Highway 45 and Mercury Street with monument box to be set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" O.D. pipe 9" below road surface in monument box with no cover at intersection of U.S. Highway 45 and Mercury Street as per highway plans.

I accepted it as the section corner since this position has been used and accepted for many years and checks with several adjacent recorded plats.

Research on file with County Remonumentation Program Representative.

ONTONAGON COUNTY
PEER APPROVED

Earl Applekamp Co. Rep.
 8-17-94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I set a 2 1/2" diameter stamped brass cap inside the found iron pipe, raised it and filled the monument box with quickrete to approximately 1 1/2" of top so a cover could still be placed on top. Set a reference monument consisting of a 2 1/2" aluminum monument 30" long with a 3" diameter stamped cap at N49°W - 37.00 feet. In addition established the following witnesses:

- Top center of fire hydrant - N39°E, 42.70 feet.
- NW corner of brick on brick-faced building - S45°E, 46.14 feet
- Found 8" nail/washer in power pole #15 - S49°W, 36.49 feet

Signed by John R Garske Date 8/29/94
 Surveyor's Michigan License No. 28410

