

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 52N R 39W	B-11
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

**SURVEY &
 REMONUMENTATION**

MAY 22 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Joseph C. Domitrovich, in a field survey on December 5, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

(B-11) 1/4 Corner Common to Sections 30 & 31, T52N, R39W

A. Description of original monument and accessories and/or subsequent restoration:

- 1845 - William A. Burt set Hemlock post
 12" Hemlock N 84° W 21 links
 18" Hemlock N 69° E 60 links
- 1921-1925 E.J. Donnelly, C.E., in a number of plats in the Village of Ontonagon, shows corner as an iron pin.
- 1961 - Victor Arcand, P.S. 10678, in Plat of Moskwa Addition to the Village Ontonagon, shows corner as a steel pin in concrete.
- 1966 - C.C. Lindgren, P.S. 14098, for M.S.H.D., shows corner as a 1/2" iron in a monument box.
- 1985 - Robert Mick, P.S. 16936, in survey for Maple Manor Nursing Home, shows corner as being an iron rod.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original corner and accessories have been destroyed by road construction.
 I found a 1/2" square iron (possibly in concrete) in a paved over monument box in centerline of 7th Street. Distance measured West to the NW Corner of Section 31 works well with surveys of record: 2690.80' measured, 2690.59' Robert Mick, 2690.64' M.S.H.D., 2692.6' Donnelly, 2696.1 GLO.

I accepted the 1/2" square iron as the 1/4 corner and raised monument box to the surface.

Research on file with County Remonumentation Representative.

Earl W. Applekamp
 COUNTY REPRESENTATIVE 12-11-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 1/2" iron pin with a 3" diameter aluminum cap stamped to read: S. 30, S. 31; T.52N, R.39W; 1/4; 1996; P.S. 37273; COUNTY REMONUMENTATION. Corner falls in a monument box. I also established a reference monument, R.M., to the East. It is a 2" x 30" aluminum pipe with a 3" diameter aluminum cap, stamped to indicate that the corner is West 30.63'

Witnesses:

Center Bolt of Gas Shut-off	N 56° E	46.06'
Top Nut of Fire Hydrant	N 79° E	27.41'
R.M.	East	30.63'
Wood Light Pole	S 43° W	41.14'
1/2" Iron in Concrete Monument	N 35° W	46.50'

NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by Joseph C. Domitrovich
 Surveyor's Michigan License No. 37273

Date 12/10/96

