

**SURVEY & REMONUMENTATION**

APR 29 1996

**COMMISSION**

JUDITH D. ROEHM  
 Ontonagon County  
 LC 3/ 336 JEM Fee: 9.00  
 10/19/95  
 13:47  
 Page 1 of 1

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in	Located In:	Corner Code #
<u>Ontonagon</u> (County)		
1. Public Land Survey	T <u>52N</u> R <u>39W</u>	<u>C-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Joseph C. Domitrovich, in a field survey on September 29, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(C-11) Corner of Sections 29, 30, 31, & 32 T52N. R39W

1845-William A. Burt set a Yellow Birch post  
 12" Hemlock S 25° W 13 links  
 12" Maple N 26° E 42 links

A 20" Hemlock line tree was marked 7.38 chains (487') south of the corner.

1966-C.C. Lindgren P. S. 14098, M.S.H.D. for M-38 Highway construction plans: Found a 1 1/2" square steel pin and established 3 new bearing trees:  
 7" Balsam N 60° W 3.40'  
 8" Maple S 10° W 20.81'  
 4" W. Birch N 65° E 23.75'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found a 1 1/2" square iron and nail and M.S.H.D. tag in Balsam stump at N 70° W 3.43' from the iron. Also found two additional Bearing trees by an unknown surveyor. The found iron matches closely the angle and distance off of centerline M-38 as noted on Highway plans. The found iron also works well with a fenceline to the South and the windthrown mound of the original Hemlock Line tree. Accepted position of iron as found and replaced with a County monument.

(Research on file with County Remonumentation Representative.)

**PEER GROUP APPROVED**  
*Paul W. Applekamp* 10-18-95  
 COUNTY REPRESENTATIVE

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Corner is an Aluminum pipe with 3" diameter stamped cap 1' west of an old fenceline to south. Corner falls at the southerly edge of clearing for Powerline.

**Witnesses:**

8" Soft Maple	S 46° E	19.65'	(Existing P.K.)
Sign Post	South	1.02'	
3" Cedar	S 25° W	28.03'	
17" Soft Maple	S 63° W	9.52'	(Existing P.K.)
Power Pole #307	N 05° W	34.50'	

**NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.**



Signed by J.C. Domitrovich Date 10/18/95

Surveyor's Michigan License No. 37273

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983