

**SURVEY &
REMONUMENTATION**

APR 29 1996

JUDITH D. ROEHM
Ontonagon County
LC 3/334 JEM Feet 9.00
10/19/95
13:41
Page 1 of 1

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>39W</u>	D-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Joseph C. Domitrovich, in a field survey on October 13, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1/4 Corner, Sections 20 and 29, T52N, T39W

1845 - William A. Burt set 1/4 section post
6" Fir N 86° E 29 links
18" Sugar N 37° W 34 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found no evidence of original corner. Found a bent rerod 3" below paved surface of Paul Bunyan Ave. The rerod falls on centerline and on the extension of a fallen fenceline to north. Corner also falls within 0.2' of a perfect split of the distance between section corners.

Accepted corner position and replaced with a county monument.

(Research on file with County Remonumentation Representative.)


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Corner is a 5/8" rerod with a 3" diameter stamped aluminum cap and falls on centerline of Paul Bunyan Ave.

Witnesses:

Power Pole	N 40° E	34.80'
12" Ash	S 35° E	45.15'
4" Ash	S 21° W	46.50'
Reference Monument (Aluminum pipe with stamped Aluminum cap)	North	25.02'
Sign Post	North	25.84'

PEER GROUP APPROVED

Earl W. Applekamp 10-18-95
COUNTY REPRESENTATIVE



NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by Joseph C. Domitrovich Date 10/18/95
Surveyor's Michigan License No. 37273