

**SURVEY & REMONUMENTATION**

APR 29 1996

JUDITH D. ROEHM  
 Ontonagon County  
 LC 3/355 JEM Feet 9.00  
 10/19/95  
 15:08  
 Page 1 of 1

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Ontonagon (County) Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T <u>52N</u> R <u>39W</u>	<u>E-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, Joseph C. Domitrovich, in a field survey on October 13, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Corner of Sections 20, 21, 28 and 29, T52N, R29W

1845 -William A. Burt set Cedar post  
 10" fir S 18° E 19 links  
 16" Hemlock N 16° W 37 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found no remaining evidence of original corner. A 4 way intersection now exists at this corner. Found no record of subsequent perpetuation. Held the intersection of centerlines of roads to north, south, east and west as the best evidence of corner position. This position works well with other corners in area.

(Research on file with County Remonumentation Representative.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Corner is a 5/8" x 24" rerod with a 3" diameter stamped aluminum cap and falls at the intersection of centerlines as noted above.

Witnesses:

Power Pole #40	N 43° E	39.29'	
Reference Monument (Aluminum pipe with stamped aluminum cap)	S 50° E	45.83'	
7" Poplar	S 60° W	78.38'	
Sign Post	S 50° E	46.35'	
Anchor Pole	N 65° W	59.68'	

PEER GROUP APPROVED

Earl W. Applebaum  
 COUNTY REPRESENTATIVE 10-18-95



NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by J. C. Domitrovich

Date 10/18/95

Surveyor's Michigan License No. 37273