

SURVEY & REMONUMENTATION

APR 29 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUDITH D. ROEHM
 Ontonagon County
 LC 3/ 359 JEM Fee: 9.00
 Page 1 of 1

| | | |
|--|---------------------------|---------------|
| For corners in <u>Ontonagon</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T <u>52N</u> R <u>39W</u> | <u>E-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

| | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

I, Joseph C. Domitrovich, in a field survey on October 17, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in line 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Standard Section Corner, Sections 32 and 33, T52N, R39W

1845 -William A. Burt set post, 16" Hemlock N 10° E 41 links
 10" Y. Birch N 40° W 5 links

Also closing corner intersected 120 links (79.20') east of this corner from township to south.

1966 -C.C. Lindgren P.S. 14098, M.S.H.D. for M-38 Highway plans, showed corner as common with twp. to south. He found a 1" iron in strawberry patch and established 3 bearing objects. He also shows distance of 5347.42' west to section corner which he also calls common.

1983 -Robert Mick P.S. 16936, in survey recorded in Liber 1, p.59 of Surveys, shows the corner witnessed by Lindgren as the closing corner, sections 5 and 4, T51N, R39W, and shows a distance (in error) of 68.64 "from original field notes", west to the standard corner sections 32 and 33, T52N, R39W. He does not show that he found or set anything at this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found the Lindgren corner and remains of his 3 bearing objects. Distance to standard corner to the west checked very well (5347.21') with Lindgren's. Determined by measurements east and west of this corner, that this corner is the closing section corner, Sections 5 and 4, T51N, R39W.

Found no remains of original standard corner. Re-established corner at record GLO distance (79.20') west of closing corner, and on line between standard corner to west and closing corner to east. Corner works well with centerline Daniel's Road to north and standard corners east and west.

(Research on file with County Remonumentation Representative.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is an aluminum pipe with a 3" diameter stamped aluminum cap and falls at the north edge of a grove of tall evergreens.

Witnesses:

| | | |
|--|---------|----------------|
| Closing Corner Sections 5 and 4, T51N, R39W, (1" iron in garden) | East | 79.20' |
| 12" Cedar | S 09° E | 18.04' |
| Sign Post | South | 2.85' |
| 14" Cherry | S 77° W | 3.94' |
| Clump of 8" Apple Trees | North | 27.74' (slope) |

PEER GROUP APPROVED

Earl W Applekamp 10-18-95
 COUNTY REPRESENTATIVE



NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by J. C. Domitrovich

Date 10/18/95

Surveyor's Michigan License No. 37273

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983