

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

JUDITH D. ROEHN
 Ontonagon County
 LC 3/349 JEM Fees 9.00
 10/19/95
 14:51
 Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>52N</u> R <u>39W</u>	<u>G-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Joseph C. Domitrovich, in a field survey on October 12, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner of Sections 15, 16, 21 and 22, T52N, R39W

1845 -William A. Burt set post

8" W. Ash S 56° W 15 links
 12" Y. Birch N 26° E 13 links

1922 -E.J. Donnelly, C.E., noted in original notes (p. 44) on file at Ontonagon County Register of Deeds, that he re-established corner position, East-West, by proportionate measurement of 3 miles between the SW corner of Section 16 and the SE corner of Section 14 (where he found bearing trees still standing). He re-established North-South position by "lining up center of road". He set a 2' iron rod in at the corner and another N 45° W, 46.9' from it.

1988 -Robert Mick P.S. 16936 in survey in Section 21 shows corner and 3 new bearing trees but does not indicate what the corner is.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a bent 1/2" iron 10" below paved surface of Lakeshore Road. Iron works well with Donnelly's distance to the west (5285.27' Donnelly vs. 5286.37' measured) and also works well with a found iron to Northwest. (N 47° W, 46.14') Corner also works well with found monuments from Mick survey, but all three of his bearing trees have been removed from road construction.

Accepted corner position and replaced with a county monument.

(Research on file with County Remonumentation Representative.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 5/8" reroed with a 3" diameter stamped aluminum cap and falls on centerline of Lakeshore road and on the centerline of 4 Mile Rock Road to the North.

Witnesses:

6" Ironwood	N 25° E	56.80'	PEER GROUP APPROVED <i>Carl W. Appeltkamp</i> 10-18-95 COUNTY REPRESENTATIVE	South 27.65'
8" Yellow Birch	S 26° E	48.81'		
Reference Monument (Aluminum pipe with stamped aluminum cap)				
Sign Post	South	28.52'		
6" White Birch	S 15° W	42.47'		
3/4" Square Twist Iron	N 47° W	46.14'		



NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by J. C. Domitrovich Date 10/18/95
 Surveyor's Michigan License No. 37273