

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

JUDITH D. ROEHM
 Ontonagon County
 LC 3/344 JEM Fee: 9.00
 Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Ontonagon Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey	T <u>52N</u> R <u>39W</u>	<u>G-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Joseph C. Domitrovich, in a field survey on October 18, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1/4 Corner Sections 33 and 34, T52N, R39W

1845 -William A. Burt set sugar post 1/4 section corner

12" Hemlock N 77° W 13 links
 10" Hemlock N 77° E 27 links (17.82')

1983 -J. Crowther, American Can Co. nailed metal tag to Maple and indicated on it that he found a "weasel" (Beaver blaze).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found the rotted remains of the original 10" Hemlock bearing tree - now approximately 24" rotted mass. Replaced corner using found bearing tree, found 2 - "beaver" blazed trees which face the re-positioned corner correctly. One of the "beaver" blazed trees has the American Can tag nailed to it.

Corner works well with section corner and 1/16 corner pipe to the north. (Wilho Aho, longtime resident to the area. remembers a wood post at this corner and a pipe at the 1/16 corner north of it. He said post was close to area American Can was running lines from.)

Corner also works well with section corner to south and blazed line to east. Placed county monument at corner position.

(Research on file with County Remonumentation Representative.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Corner is an aluminum pipe with a 3" diameter stamped aluminum cap.

Witnesses:

4" Hard Maple	N 70° E	18.40'		
Twin 14" Soft Maple	S 61° E	13.50'		
5" Hard Maple with "Beaver Blaze" and American Can Co. Tag.	S 13° W	6.55'		
12" Poplar with "Beaver Blaze"	S 60° W	5.29'		
Sign Post	North	0.90'		

PEER GROUP APPROVED

Paul W. Applekamp
 10-18-95
 COUNTY REPRESENTATIVE



NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by J. C. Domitrovich

Date 10/18/95

Surveyor's Michigan License No. 37273

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1993