

JUDITH D. EDEHM 1P
Ontonagon County

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Ontonagon County Remonumentation Corner

of 1 10 54 99
 Rec. Date 06/25/98 Time 12:12
 RECORDING FEE: 9.00

SURVEY &
 REMONUMENTATION
 JAN 11 1998
 SECTION

For corners in

Ontonagon County	Located in:	Corner Code #
1. Public Land Survey	T52N R39W	J-5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Joseph C. Domitrovich, in a field survey on June 1, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(J-5) 1/4 Corner Common to Sections 11 & 14, T52N, R39W

- 1845 - William A. Burt set Cedar post
 12" Hemlock N 42° E 15 links
 30" Hemlock N 25° W 15 links
- 1948 - Ned Hawley, timbercruiser, noted in his personal copy of the original field notes that he found a cedar stake here 84 paces West of old road and that he placed a pipe at its location. He notes that the stump of the original Hemlock bearing tree agreed with this position.
- 1981 - Robert A. Mick, P.S. 16938, recorded this corner in Liber 2, Page 1 of Corner Records. He found a 1" iron pipe and witnessed 3 new bearing trees.
 6" Cedar S 77° W 15.00'
 6" Cedar N 34° W 15.00'
 4" Cedar N 82° E 14.50'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found the pipe called for by Hawley 86 feet West of a gravel road. I found the rotted remains of the original 12" Hemlock bearing tree with axa marks on the measuring notch still visible. I also recovered Bob Mick's bearing trees. His 6" Cedar to the Northwest is actually a 6" Balsam, now dead. Distances to the Sections Corners East and West work well. I accepted the iron pipe as the 1/4 Corner.

SW Corner Section 11	S 89° 55' 38" E	2616.38'
SE Corner Section 11	S 89° 09' 48" W	2616.04'

Research on file with County Remonumentation Representative.

Carl W. [Signature]
 COUNTY SURVEYOR
 6-17-98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 1/2" x 48" iron pin with a 3" diameter aluminum cap driven into the 1" iron pipe, stamped to read: COUNTY REMONUMENTATION; S. 11, S. 14; 1/4; T. 52N, R. 39W; 1998; P.S. 37273.

Witnesses:

6" Balsam (dead)	N 34° W	15.04'	(existing nail)
14" Hemlock	N 19° W	9.50'	
6" Cedar	N 85° E	14.36'	(existing nail)
6" Cedar	S 30° E	18.54'	
8" Cedar	S 80° W	14.99'	(existing)
Steel Sign Post	West	1.57'	

NOTE: Bearings to witness objects are magnetic. Distances are to a nail in side of the witness object.

Signed by J. C. Domitrovich

Date 6-17-98

Surveyor's Michigan License No. 37273

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN. 1983
 REVISED OCT., 1995

