

SURVEY & REMONUMENTATION

APR 25 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

ONTONAGON
(County)

Located In:

Corner Code #

| | | | | | |
|------------------------------------|---|----|---|----|-----|
| 1. Public Land Survey | T | 52 | R | 39 | K-3 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

Recorded December 5 1994
at 2:05 o'clock P. M. in
Liber 3 page 220
J. M. M... deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Section Corner 1, 2, 11, & 12, T52N R39W

I, Earl W. Applekamp in a field survey on October 11, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner established by William Burt, Deputy Surveyor, September 1845.
Set Tamarack Post.

Original Bearing Trees:

| | | | | |
|------------|-----|-------|-----------|-----------|
| Tamarack | 6" | S40°E | 1.23 Chs. | (81.18') |
| White Pine | 10" | N77°W | 2.27 Chs. | (149.82') |

ONTONAGON COUNTY

PEER APPROVED

EW Applekamp
Ont Co Rep

11-30-94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

At the corner location I found a 1" pipe. The location agreed with the calls on the original field noted. This corner is identified in several surveys in the area. I accepted the position as being the original location based on the above information.

Research on file with County Remonumentation Program Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I placed a 3/4"x12' aluminum rod into the existing 1" pipe and placed a 3 1/4" cap on the rod stamped to read: County Remonumentation, S2, S1, S11, S12, T52N R39W, 1994, P.S. 17610. I established the following bearing trees and reference objects.

| | | | | | | |
|----------------|-------|---------|---|-----------------|-------|---------|
| 15" Red Pine | N44°W | 134.02' | - | 9" Maple | S46°W | 130.41' |
| 13" White Pine | S85°W | 108.00' | - | Steel Sign Post | N68°E | 1.60' |



Signed by Earl W. Applekamp

Date November 11, 1994

Surveyor's Michigan License No. 17610