

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Ontonagon County Remonumentation Corner

Ontonagon County
of 1 LC 5/ 99
Rec. Date 06/25/98 Time 12:12
RECORDING FEE: 9.00

For corners in

Table with columns: Ontonagon County, Located in, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

SECTION

JAN 11 1999

SECTION

Register of Deeds Stamp & File Number

I, Joseph C. Domitrovich, in a field survey on June 8, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: (K-4) 1/4 Corner Common to Sections 11 & 12, T52N, R39W

1845 - William A. Burt set Cedar post in open marsh. 7" Fir N 01° W 2.84 chains

1954 - Ned and John Hawley noted in their personal copy of the original field notes that they put a 14 foot long 1/2" galvanized pipe painted yellow at old 1/4 Corner. It was 6 feet above the snow.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found no remains of original corner or accessories. After an extensive search, I was unable to find the remains of Hawley's 14 foot long pipe. The area around the corner is very wet and boggy, an open marsh, with five foot high willow scrub brush and is not a pleasant place to be.

I re-established this corner by single proportionate measurement. It works well with Section Corners to North and South.

Research on file with County Remonumentation Representative.

PEER GROUP APPROVED
Earl W. Speltkamp
COUNTY REPRESENTATIVE 6-17-98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 1/4" x 10' aluminum rod with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; S.11, S. 12; 1/4; T.52N, R.39W; 1998; P.S. 37273. Corner falls 240 +/- feet North of North edge of Flintsteel River and 250 +/- feet West of East edge Flintsteel River.

Witnesses:

Table with columns: Witness, Bearing, Distance, and Note. Includes Steel Sign Post West (3.28' to face), Steel Sign Post East (3.26' to face), SE Cor. Section 11 (S 00° 08' 45" E, 2634.69'), NE Cor. Section 11 (N 00° 08' 45" W, 2634.69'), SWly Cor. of Red Cabin on East Side of River (N 55° 50' E, 1108.1', no nail).

No other ties available



NOTE: Bearings to witness objects are magnetic. Distances are to a nail in side of the witness object unless noted.

Signed by Joseph C. Domitrovich

Date 6-17-98

Surveyor's Michigan License No. 37273